

ENERGY EFFICIENCY OPPORTUNITIES  
DETAILED ASSESSMENT REPORT

WAMBO COAL PTY LIMITED



August 2008

Denis Cooke & Associates Pty Limited  
PO Box 4741 North Rock NSW 2151  
Ph: 02 9871 6641, Fx: 02 9614 1723  
Web: [www.decoa.com.au](http://www.decoa.com.au)  
Email: [denis@decoa.com.au](mailto:denis@decoa.com.au)



Description	Date	Prepared by	Approved by
Draft for Approval	29 August 2008	Denis Cooke	
E Mass Bal & extra Costs added	20 November 2008	Denis Cooke	
KPI review data added, benchmarking energy review process reference added	5 December 2008	Denis Cooke	Scott Sullivan, General Manager

**TABLE OF CONTENTS****Contents**

Executive Summary:.....	1
Background:.....	3
Introduction:.....	4
Key Element 1: Leadership.....	4
Key Element 2: People.....	4
Key Element 3: Information, Data and Analysis.....	4
Key Element 4: Opportunity Identification and Evaluation.....	5
Key Element 5: Decision making.....	5
Key Element 6: Communicating outcomes.....	5
Integrating the EEO Assessment with ESAP and GHCP:.....	5
Approach Taken with This Assessment:.....	7
Wambo’s Performance and the Six Key Elements:.....	8
Assessment Report:.....	15
Overview and Introduction to Wambo Operations:.....	15
Peabody Energy:.....	15
Wambo Coal:.....	15
Site Energy Use, Costs and Production:.....	18
Energy Use:.....	18
Electricity Use:.....	18
Diesel Use:.....	19
Total Energy Use and Costs:.....	21
Production:.....	22
Total Energy Costs per Production Unit:.....	23
Key Performance Indicators:.....	25
Total Energy Use per BCM and per Tonne ROM:.....	26
Total Energy Use per Bank Cubic Metre TEM:.....	26
Total Energy Use versus Tonnes ROM:.....	27
Total Energy Use per Tonne ROM versus Tonnes ROM:.....	27
Diesel Energy Use MJ per Bank Cubic Metre TEM:.....	28
Diesel Energy Use versus Bank Cubic Metres TEM:.....	28
Diesel Energy per BCM:.....	29
CH&PP – Electrical Energy kWh per Tonne ROM Feed:.....	29
CH&PP – Electrical Energy kWh versus Plant Input (Tonnes ROM)......	30
CH&PP – Electrical Energy kWh per Tonne ROM Feed versus Plant Input (Tonnes ROM):.....	30
Site Energy Demand and Distribution:.....	32
Electrical Energy Demand:.....	32
Electrical Energy Distribution:.....	38
Main Site:.....	38
CH&PP:.....	42
Diesel Energy Demand and Distribution:.....	45
Site Energy Mass Balance:.....	49
Energy Savings Measures:.....	51
Actions taken over previous Five Years:.....	51
15 km Rail Loop replacing trucks for Clean Coal Loadout:.....	51

Use of VSDs on Maingate 1 Conveyor Drive Head:.....	52
Use of High Efficiency Motors:.....	52
Power Factor Correction (PFC) in CH&PP:.....	53
Cost-Effective Opportunities: .....	53
Use of VSDs on Maingate 1 Conveyor Tripper 1: .....	53
PFC on North Wambo Underground: .....	54
Turn off Wollemi U/G Fans, Sump Pump and Decommission: .....	54
Elimination of 220kW ROM Pump: .....	55
Installation of Additional VSDs on Thickener Underflow Pumps:.....	55
Installation of a VSD on the Module 1 Desliming Cyclone Feed Pump: .....	56
Installation of a VSD on the Module 1 Dense Medium Cyclone Feed Pump: .....	56
Use of HEM Motors in the new CH&PP:.....	57
New Clean Coal Stack-out Conveyor to Reduce Dozer Diesel Use:.....	58
Potential Cost-Effective Opportunities:.....	59
Use of VSDs on Maingate 2 Conveyor: .....	59
Use of VSDs on Maingate 3 Conveyor: .....	59
Alternative conveyor route to from Underground to CH&PP:.....	60
Beneficial use of Coal Seam Methane:.....	61
Installation of a VSD on the Module 2 Desliming Cyclone Feed Pumps: .....	61
Installation of a VSD on Module 2 Dense Medium Cyclone Feed Pump: .....	62
VSD on Circulating Medium Pumps:.....	62
Additional Power Factor Correction (PFC) in CH&PP:.....	62
Scheduling Water Management Pumps to minimise Demand Charges: .....	63
Electrical Metering Systems Upgrade for CH&PP and U/G 11 kV Switchboards: ....	63
Site Wide Diesel Fuel Management System:.....	64
Open Cut Operations EEO projects: .....	65
CI Projects.....	67
CI Projects – Longwall: .....	67
CI Projects – Development: .....	69
CI Projects – Maintenance:.....	72
CI Projects – CH&PP: .....	74
Reference Documents: .....	75